


Grabber Construction Products, Inc.
Design No. JWA/PHV 120-04
Horizontal or Vertical Floor/Ceiling and Wall Assembly
****Fire Rated Non-Flammable Acoustic Firestop Sealant**
Test Standards: ASTM E814, UL 1479, ULC S115
Test Furnace Internal Positive Pressure Differential – 2.5 Pa (0.01 in. of water) Minimum
Rating: 2 Hour

	Fire "F" Rating	Fire/Hose "FH" Rating	Temp "FTH" Rating
ASTM E814	2 Hour	2 Hour	2 Hour
CAN/ULC S115	2 Hour	2 Hour	2 Hour



1. **PENETRATING ITEM:** Not applicable.
2. **FLOOR/CEILING OR WALL FIRE SEPARATIONS:**
1 and 2 hour rated ASTM E-119 or CAN/ULC S101 concrete, metal, or wood framed fire-rated gypsum wall board (GWB) floor/ceiling/wall assemblies.
3. **FIRESTOP SYSTEM COMPONENT 1:** Grabber Construction Products, Inc. – GrabberGard EFC* or GrabberGard IFC* firestop sealant at a min. bead diameter of 3/8 in. (10mm), caulked

into the corner and behind the GWB around the entire perimeter of the fire-rated wall assembly. Attach gypsum wall board (GWB) membranes into the sealant within 15 min. of sealant placement or prior to sealant skinning.

4. **FIRESTOP SYSTEM COMPONENT 2:** Filler material not required.

*WH Labeled Component

**The acoustic claims have not been verified by Intertek Testing Services